

CEMCO, Inc.
Rt. 3, Box 14
Olney, TX 76374-9740
Phone: 855-564-5855
Fax: 940-564-5546
www.cemcoinc.com

CEMCO, INC. MODEL 275 3D MOBILE BATCH PLANT,
COMPLETE WITH JONEL ARCHER COMPUTER SYSTEM.

SPECIFICATIONS:

173 HP DIESEL ENGINE
200 GALLON HYDRAULIC TANK
2 EACH 13 CUBIC YARD ROCK BINS
10 CUBIC YARD SAND BIN
265 SQ. FT. CARTRIDGE - PULSE JET DUST COLLECTOR
58 TON CEMENT STORAGE
660 GALLON WATER SURGE BIN
400 GALLON WATER WEIGH BIN
100 CUBIC FT. CEMENT WEIGH BIN
100' CABLES FOR BATCH HOUSE
SUPPORT SCREW JACKS (10)
HYDRAULIC LEVELING JACKS (4)
CEMENT WEIGH BIN PULSE JET DUST COLLECTOR (25 SQ. FT.)
BIN TIE-DOWNS (4)
30" X 35 DEGREE TROUGH CONVEYOR
5 BANK LEVELING & ERECTION VALVE
WEIGHT 55,000 LBS. (ESTMIATED)
2" 160 GPM HYDRAULIC POWER WATER PUMP
50 CFM AIR COMPRESSOR
91 GALLON DIESEL FUEL TANK
WATER FILL VALVE 6"
WATER DISCHARGE VALVE 6"
CEMENT FILL VALVE 12"
CEMENT DISCHARGE VALVE 10"
CONVEYOR BELT SPEED - VARIABLE 400 FPM MAX
BELT CAPACITY @ 400 FPM - 800 TPH
NORMAL 10 YARD DISCHARGE TIME 1.5 TO 2 MINUTES
(STANDARD PLANT READY TO ADD 3 FEEDER BELTS AND 1 AUXILIARY SILO)